Republic of the Philippines
CAGAYAN DE ORO CITY WATER DISTRICT
Corrales Avenue, Brgy. 27, Cagayan de Oro City, Misamis Oriental

SUPPLEMENTAL NOTICE No. 1
for
1 LOT WATER SUPPLY SYSTEM OF NHA LUMBIA HEIGHTS PHASE 1 RELOCATION SITE, PAHIRON, LUMBIA, CAGAYAN DE ORO CITY
(PR No. 22-09-07-0148)
November 16, 2022

AS POSTED				***SHOULD BE READ AS***			
FOR: SECTION VI. SPECIFICATIONS; SECTION VIII. BILL OF QUANTITES (BOQ); AND BID FORM NO. 2 (BOQ)				**FOR: SECTION VI. SPECIFICATIONS; SECTION VIII. BILL OF QUANTITES (BOQ); AND BID FORM NO. 2 (BOQ)**			
H. THREE (3) UNITS 100MMØ RESIDENTIAL FIRE HYDRANT ASSEMBLY W/ BARRICADE				**H. THREE (3) UNITS 100MMØ RESIDENTIAL FIRE HYDRANT ASSEMBLY W/ BARRICADE**			
Flange Tee	100mmØ x 100mmØ	3	pcs	Flange Tee	100mmØ x 100mmØ	3	pcs
Resilient Gate Valve for water, two (2) stages of double O-ring, ductile iron/epoxy coated body, stainless steel shaft, flange type, non-rising stem, complete with accessories	100mmØ	3	sets	Resilient Gate Valve for water, two (2) stages of double O-ring, ductile iron/epoxy coated body, stainless steel shaft, flange type, non-rising stem, complete with accessories	100mmØ	3	sets
Universal Adaptor	100mmØ	6	pcs	Universal Adaptor	100mmØ	6	pcs
B.I Pipe, Sched 40	100mmØ x 6m x 6.02mm thk	2	lgths	B.I Pipe, Sched 40	100mmØ x 6m x 6.02mm thk	2	lgths
Single Fire Hydrant head	100mmØ	3	pcs	Single Fire Hydrant head	100mmØ	3	pcs
Hinges CI Frame		6	pcs	Hinges CI Frame		6	pcs
Steel Bend w/ Ring Flange @ both ends	**100mmØ x 90°**	**3**	pcs	**(DELETED)**			
Ring Flange	100mmØ	6	pcs	Ring Flange	100mmØ	6	pcs
Capscrew with Nut and Lock-Washer, full threaded	5/8"Ø x 3"	120	kgs	Capscrew with Nut and Lock-Washer, full threaded	5/8"Ø x 3"	120	pcs
Rubber Gasket	1/4" thk	5	pcs	Rubber Gasket	1/4" thk	5	kgs
Valve Box Cover	150mmØ	3	lgth	Valve Box Cover	150mmØ	3	pcs
uPVC Pipe Casing, for Valve Box	150mmØ	1	kgs	uPVC Pipe Casing, for Valve Box	150mmØ	1	lgth
Welding Rod	E6012	10	bags	Welding Rod	E6012	10	kgs
Portland Cement	40kg/bag	3	cu.m	Portland Cement	40kg/bag	3	bags
Washed Sand		0.5	cu.m	Washed Sand		0.5	cu.m
Crushed Gravel	3/4"	0.5	gal	Crushed Gravel	3/4"	0.5	cu.m

Nikki.Belen
11/15/2022 2:34 PM

QDE Paint	Yellow	1	gal	QDE Paint	Yellow	1	gal
	Black	1	gal		Black	1	gal
Paint Thinner		1	gal	Paint Thinner		1	gal
Red Oxide Primer		2	pcs	Red Oxide Primer		2	gal
Paint Brush	2"	2	pcs	Paint Brush	2"	2	pcs

Prepared by:

JUSTINE NICOLE C. BELEN
BAC Secretariat Staff

Checked by:

JOSEPH A. MAGRIÑA
Head, BAC Secretariat

Noted by:

ANTONIO B. YOUNG
BAC A Chairman

Nikki.Belen
11/15/2022 2:34 PM